

Subdivisions of T. 3 North, R. 33 East

Chains	<p>No timber. Poor grass.</p> <hr/> <p>South bet. Secs. 22 and 23.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Commencing at $\frac{1}{4}$ sec. cor. bet. Secs. 22 and 23 which is a stone 10x12x8 ins. buried in the ground with mound of earth and pits.</p> <p>1.00 Descend.</p> <p>13.90 Set basalt stone 14x10x10 ins. 10 ins. in the ground for Meander cor. to fractional Secs. 22 and 23, marked M. C. with T 3 N U R on S., R 33 E S 23 on E. and S 22 on W. faces, and dug a pit 3 ft. square, 12 ins. deep, 8 lks. S. of cor. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Cor. is on S. side of Wild Horse creek, 20 lks. dist.</p> <p>17.25 O. R. and N. Railway, course E. and W.</p> <p>18.50 Wagon road, course E. and W. Ascend.</p> <p>28.00 Top of ridge, course NW. +100</p> <p>32.50 Gulch, course NW. -50</p> <p>40.00 Set basalt stone 24x18x10 ins., 18 ins. in the ground for cor. to Secs. 22, 23, 26 and 27, marked with 2 notches on S. and E. edges, dug pits 18x18x12 ins in E. sec., $5\frac{1}{2}$ ft., dist., raised mound of earth 2 ft. high, 4 ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Not cultivated.</p> <p>No timber. Short grass.</p> <hr/> <p>East on random bet. Secs. 23 and 26.</p> <p style="text-align: center;">Va. 20° East.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor. and at</p> <p>80.00 Intersect N. and S. line 45 lks. N. of cor. to Secs. 23, 24, 25 and 26. Thence N. 89° 41' W. on true line.</p> <p style="text-align: center;">Va. 21° East.</p> <p>37.00 Wagon road, course E. and W.</p>
--------	--