

Subdivisions of T. 3 North, R. 33 East

Chains 40.00	Set basalt stone 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
80.00	Cor. to Secs. 22, 23, 26 and 27. Land, slightly rolling. Soil, 1st rate. Uncultivated. No timber. Poor grass.
South bet. Secs. 26 and 27. Va. 20° East.	
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. And in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.
60.00	Wagon road, course E. and W.
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 26, 27, 34 and 35, dug pits 18x18x12 ins. in each sec., $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in SE. pit drove stake 2 ft. long, 2 ins. square, 12 ins in the ground, marked T 3 N S 26 on NE., R 33-E S 35 on SE., S 34 on SW., and S 27 on NW. faces, with 1 notch on S. and 2 notches on E. edges. Land, level. Soil, 1st rate. Uncultivated. No timber. Poor grass.
East on random bet. Secs. 26 and 35. Va. 20° East	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at
79.70	Intersect N. and S. line 56 lks. N. of cor. to Secs. 25, 26, 35 and 36. Thence N. 89°36' W. on true line. Va. same
39.85	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$