

Subdivisions of T. 3 North, R. 33 East

Chains		
40.00	Not finding any trace of $\frac{1}{4}$ sec. cor. I set temporary $\frac{1}{4}$ sec. corner and at	
80.25	A point 70 lks.S. of cor. to Secs. 20, 21, 28 and 29 Thence S. 89°30' E. on true line. Va. 20° East.	
5.15	Ravine S.	-50
27.15	Ravine S.	-60
40.12	Set basalt stone 16x10x8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, dug pits 18x18x12 E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. Descend.	
42.00	Wagon road NE. and SW.	
44.05	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to fractional secs. 21 and 28, marked M C U R with T 3 N on E., R 33 E S 21 on N., and S 28 on S. faces, dug a pit 3 ft. square, 1 ft. deep, 8 lks. E. of post and raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base around it on E. bank of Wild Horse creek 10 lks. wide, course SW.	
55.00	R. R. O. R. and N., Co. SW and ascend bluff	+50
80.25	Cor. to Secs 21, 22, 27 and 28. Land, hilly, rolling. Soil, 2nd rate; not cultivated. No timber nor grass.	
	South bet. Secs. 27 and 28. Va. 20° East	
26.70	Wagon road in gulch NW.	-50
40.00	Set basalt stone 16x10x10 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.	
79.00	Trail NW.	
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 27, 28, 33 and 34, and dug pits 18x18x12 ins.	