

Subdivisions of T. 3 North, R. 33 East

Chains	<p>in each sec., 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it and in SE. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 27 on NE., R 33 E S 34 on SE., S 33 on SW and S 28 on NW faces, with 1 notch on S. and 3 notches on E. edges.</p> <p>Land, level.</p> <p>Soil, good. No cultivated.</p> <p>No timber. Poor grass.</p>
	<p>East on random bet. Secs. 27 and 34.</p> <p style="text-align: right;">Va. 20° East.</p>
40.00	Set temporary ¼ sec. cor. and at
79.50	<p>Intersect N. and S. line 50 lks. S. of cor. to Secs. 26, 27, 34 and 35. Thence</p> <p>S. 89°39' W. on true line.</p> <p style="text-align: right;">Va. same</p>
35.00	Wagon road SW.
39.75	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on N. face.</p>
79.50	<p>Cor. to Secs. 27, 28, 33 and 34.</p> <p>Land, level.</p> <p>Soil, 1st rate. Not cultivated.</p> <p>No timber. Poor grass.</p>
	<p>South on true line bet. Secs. 33 and 34.</p> <p style="text-align: right;">Va. 20° East.</p>
15.00	Wagon road, course NW.
23.50	Wagon road to Centerville, NE.
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor., dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long,</p>