

Subdivisions of T. 3 North, R. 33 East

Chains	ft. base around it.	
60.00	Wild Horse creek.	
61.00	Wagon road, course SW.	
79.20	Cor. to Secs. 29, 30, 31 and 32. Land, mostly level. Soil, 1st rate. Partly cultivated. No timber.	
South on true line bet. Secs. 31 and 32. Va. 20° East.		
12.20	O.R. and N. Railway, SE.	
22.40	Set post on N. bank of Wild Horse, 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to secs. fractional 31 and 32, marked M C U R with T 3 N on N., S 32 R 33 E on E., and S 31 on West faces, dug a pit 3 ft. square, 1 ft. deep, 8 lks. N. of post, and raised mound of earth 2 ft. high, 4½ ft. base around it.	
24.50	Wild Horse creek 10 lks. wide, course SE.	
29.64	Wagon road, course SW.	
32.50	Top of hill, course W.	+100
39.50	Canyon	-75
40.00	Set basalt stone 12x10x8 ins., 8 ins. in the ground for ¼ sec. cor., marked ¼ on W. face, dug pits 18x18x12 ins. N. and S. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it. Ascend	
79.36	Intersect S. bdy., Township line 300 lks. E. of cor. to Secs. 5 and 6, T. 2 N., R. 33 E. and set post 4 ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to Secs. 31 and 32, marked C C., T 3 N R 33 E on N., S 32 on E., and S 31 on W. faces, with 5 notches on E. and 1 notch on W. edges, dug pits 18x18x12 ins. NE. and W. of post, 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base around it. Land, rolling. Soil, 1st rate. Uncultivated.	