

Sub-Subdivisions of T. 3 North, R. 33 East

| | |
|--|--|
| Chains 59.17 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 78.90 | <p>To 1/16 sec. corner at place of beginning. Land, rolling, Hills. Soil, 1st rate. Not cultivated.</p> |
| <p>East on random through center of Sec. 36. Va. 20¼ ° East.</p> | |
| 78.80 | <p>Commencing at ¼ sec. cor. between Secs. 35 and 36. Set temporary cors. at 20.40 and 60 chains and at Intersect E. bdy. 42 lks. S. of ¼ sec. cor. Thence S. 89°42' W. on true line.</p> |
| 19.70 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 in. in the ground, marked 1/16 S on N. face.</p> |
| 39.40 | <p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p> |
| 50.50 | <p>Canon and road.</p> |
| 59.10 | <p>Set charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 78.80 | <p>To point of beginning.</p> |