

Sub-Subdivisions of T. 3 North, R. 33 East

| | |
|---|--|
| Chains | <p>Land, rolling.</p> <p>Soil, good. Bunch grass</p> |
| <p>East on random through N. $\frac{1}{4}$ of Sec. 36.</p> <p align="center">Va. 20° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains S. or NW. cor. of sec. 36 and set temporary cors. at 20.40 and 60 chains and at</p> | |
| 78.82 | <p>Intersect E. bdy. 60 lks. S. of 1/16 sec. cor. Thence S. 89°34' W. on true line.</p> |
| 19.70 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 39.41 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 59.11 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 78.82 | <p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, good. Not cultivated.</p> <p align="right">Oct. 26th 1887</p> |