

Township 4 North, Range 34 East

<p>Chains 13.54</p>	<p>Wild Horse Creek 10 links wide, course South West.</p>	<p>-10</p>
<p>40.00</p>	<p>Set <math>\frac{1}{4}</math> section post corner. Drove charred stake, dug pits and raised mound as per instructions.</p>	
<p>80.00</p>	<p>Set post corner for sections 34 &amp; 35, 2 &amp; 3. Drove charred stake, dug pits and raised mound as per instructions.  Land, gently rolling prairie. Good grass. Soil, 1st rate.</p>	
<p>East on South boundary of Section 35.</p>		
<p>Var. 20°30' East.</p>		
<p>40.00</p>	<p>Set <math>\frac{1}{4}</math> section post corner. Drove charred stake, dug pits and raised mound as per instructions.</p>	
<p>80.00</p>	<p>Set post corner for sections 35 &amp; 36 also 1 &amp; 2, T. 4 N., R. 34 E. Drove charred stake, dug pits and raised mound as per instructions.  Land, rolling prairie. Good grass. Soil, good 2nd rate.</p>	
<p>East on South boundary of Section 36.</p>		
<p>Var. 21° East.</p>		
<p>40.00</p>	<p>Set <math>\frac{1}{4}</math> section post corner. Drove charred stake, dug pits and raised mound as per instructions.</p>	<p>+ 10</p>
<p>80.00</p>	<p>Set post corner for Townships 3 &amp; 4 North of Ranges 34 &amp; 35 East, Sections 1, 6, 31 &amp; 36. Drove charred stake, dug pits and raised mound as per instructions.  Land, rolling. Good grass. Soil, 2nd rate.</p>	
<p>Survey of the Exterior lines of Township number 3 North of Range 35 East of Willamette Meridian in the State of Oregon by William H. Odell, deputy Surveyor, under his contract No. 114, bearing date July 2nd 1866.</p>		
<p>West Boundary of Township 3 North, R. 35 E.</p>		
<p>South on West boundary of Section 6.</p>		
<p>40.00</p>	<p>Set <math>\frac{1}{4}</math> section post corner. Drove charred stake, dug pits and raised mound as per instructions.</p>	<p>-10</p>