

Township 3 North, Range 35 East

Chains 80.00	Set post corner for sections 6, 7, 1 & 12. Drove charred stake, dug pits and raised mound as per instructions. Land, rolling prairie. Good grass. Soil, 2nd rate.	-15
21.50	South on West boundary of Section 7. Var. 20° East. Small branch 4 lks. wide, course NW.	-15
40.00	Set $\frac{1}{4}$ section post corner, drove charred stake, dug pits and raised mound as per instructions.	+20
80.00	Set post corner for sections 7, 18, 12 & 13. Drove charred stake, dug pits and raised mound as per instructions. Land, gently rolling prairie. Soil, good 2nd rate.	
40.00	South on West boundary of Section 18. Var. 20°30' East. Set $\frac{1}{4}$ section post corner. Drove charred stake, dug pits and raised mound as per instructions.	
60.00	Spring branch 3 lks. wide, course North West.	
80.00	Set post corner for sections 18, 19, 13 & 24. Drove charred stake, dug pits and raised mound as per instructions. Land, gently rolling prairie. Good grass. Soil, 1st rate. July 26th 1866.	
1.00	South on West boundary of Section 19. Var. 20°30' East. Stage road from Boise City to Umatilla, course North West and South East.	
40.00	Set $\frac{1}{4}$ section post corner. Drove charred stake, dug pits and raised mound as per instructions.	+15
80.00	Set post corner for sections 19, 30, 24 & 25. Drove charred stake, dug pits and raised mound as per instructions.	-5