

. Township 3 North, Range 34 East W. M.

Chains	West between Sections 9 & 16.  Var. 21° East.	
40.00	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.	-15
80.00	Set post corner for sections 8, 9, 16 & 17. Drove charred stake, dug pits and raised mound as per instructions. Land, gently rolling. Good grass. Soil, 2nd rate.	
<hr/>		
	North between Sections 8 & 9.  Var. 21° East.	
19.85	Wild Horse Creek 10 lks. wide, course SW.	
40.00	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post corner for sections 4, 5, 8 & 9. Drove charred stake, dug pits and raised mound as per instructions. Land, gently rolling. Good grass. Soil, 1st rate.	
<hr/>		
	East on random between Sections 4 & 9.  Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ section post corner.	
79.85	Intersected North and South line 30 links North of post corner.  N. 89°47' W. on true line.	
17.25	Wild Horse Creek 10 links wide, course SW.	
39.92	Set post corner $\frac{1}{4}$ section, drove charred stake, dug pits and raised mound as per instructions.	
79.85	To post corner.  Land, gently rolling. Good grass. Soil, good 2nd rate.	
<hr/>		
	North on random between Sections 4 & 5.	
40.00	Set temporary $\frac{1}{4}$ section post corner.	
79.81	Intersected East and West line 40 links West of post cor. S. 0°17' East on true line.	
39.81	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.	