

Township 3 North, Range 34 East W. M.

Chains

Land, rolling. Good grass.
Soil, good 2nd rate.

South between Sections 16 & 17.

37.50 Boise City and Umatilla Stage Road, course W.

40.00 Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instruction.

80.00 Set post corner for sections 16, 17, 20 & 21. Drove charred stake, dug pits and raised mound as per instructions.

Land, gently rolling. Good grass.

Soil, good 2nd rate. August 30th 1866.

West between Sections 17 & 20.

Var. 20°30' East.

40.00 Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.

80.00 Set post corner for sections 17, 18, 19 & 20. Drove charred stake, dug pits and raised mound as per instructions.

Land, rolling. Good grass.

Soil, good 2nd rate.

West on random between Sections 18 & 19.

Var. 20°30' East.

40.00 Set temporary $\frac{1}{4}$ section post corner.

80.00 Could not find corner on Town line for sections 13, 24, 18 & 19. No stake or mound visible near the place where the line ought to be, consequently set post, drove charred stake, dug pits and raised mound as per instructions.

East on true line.

40.00 Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions

80.00 To post corner.

Land, gently rolling. Good grass.

Soil, good 2nd rate.