

Township 3 North, Range 34 East W. M.

Chains	North between Sections 17 & 18.	
39.75	Boise City and Umatilla Stage Road, course East & West.	
40.00	Set post corner for $\frac{1}{4}$ section corner, Drove charred stake, dug pits and raised mound as per instructions.	
47.40	Wild Horse Creek 10 links wide, course SW.	-25
80.00	Set post corner for sections 7, 8, 17 & 18. Drove charred stake, dug pits and raised mound as per instructions.	+30
	Land broken. Grass good.	
	Soil, good 2nd rate.	

	East on random between Sections 8 & 17.	
	Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ section corner.	
79.89	Intersected North and South line 41 links South of post corner.	
	S. 89°42' W. on true line.	
25.10	Wild Horse Creek 10 links wide, course SW.	-15
39.94	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.	
79.89	To post corner.	
	Land, rolling. Grass good.	
	Soil, good 2nd rate.	

	West on random between Sections 7 & 18.	
40.00	Set temporary $\frac{1}{4}$ section corner.	
80.12	Intersected North and South line 15 links South of post corner	
	N. 89°54' East on true line.	
40.12	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.	
80.12	To post corner.	
	Land, rolling. Grass good.	
	Soil, 2nd rate.	

	North between Sections 7 & 8.	