

Subdivisional Lines of Township No. 3 N., R. 34 E. W. M.

Chains	
	<p>13 & 14.</p> <p>Land, level.</p> <p>Soil, 1st rate. Good grass.</p>
	<p>East on random bet. Secs. 13 & 24.</p> <p style="text-align: right;">V. 20°30' E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersected N. & S. line 14 lks. S. of cor.
	S. 89°54' W. on true line.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	To corner.
	<p>Land, level.</p> <p>Soil, good.</p>
	<p>North bet. Secs. 13 & 14.</p>
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 13, 14, 11 & 12.
	<p>Land, level.</p> <p>Soil, good. Good grass.</p>
	<p>East on random bet. Secs. 12 & 13.</p> <p style="text-align: right;">V. 21° E.</p>
40.00	Set temporary $\frac{1}{4}$ sec. corner.
79.86	Intersected N. & S. line 14 lks. S. of cor.
	S. 89°54' W. on true line.
39.93	Set post and made earth mound for $\frac{1}{4}$ sec. corner.
79.86	To corner.
	<p>Land, rolling.</p> <p>Soil, good. Good grass.</p>
	<p>North bet. Secs. 11 & 12.</p>
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
43.50	Dry Branch, course W.
80.00	Set post and made earth mound for cor. to Secs. 11, 12, 1 & 2.
	<p>Land, rolling.</p> <p>Soil, good. Good grass.</p>