

Subdivisional Lines of Township 3 North, R. 34 E.W. M.

Chains	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made earth mound for cor. to Secs. 21, 22, 15 & 16.
	Land, level.
	Soil, good.
East on random bet. Secs. 15 & 22.	
V. 21° E.	
40.00	Set temporary $\frac{1}{4}$ S. cor.
80.00	Intersected N. & S. line 14 lks. S. of cor. S. 89°54' W. on true line.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	To corner.
	Land, level. Good grass.
	Soil, good.
North bet. Secs. 15 & 16.	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made earth mound for cor. to Secs. 15, 16, 9 & 10.
	Land, level.
	Soil, good.
East on random bet. Secs. 10 & 15.	
Var. 20°30' E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.92	Intersected N. & S. line at cor. W. on true line.
39.96	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
79.92	To corner.
	Land, level.
	Soil, good.
North bet. Secs. 9 & 10.	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made earth mound for cor. to Secs. 9, 10, 3 & 4.
	Land, some rolling.