

Subdivisional Lines of Township 3 North, R. 34 E. W. M.

Chains	
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.00	Intersected N. & S. line 12 lks. N. or corner. N.89°55' W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ sec. cor.
80.00	To corner. Land, rolling. Soil, good.
<hr/>	
	North bet. Secs. 8 & 9.
19.75	To Wild Horse ck., the boundary of the Reservation.
<hr/>	
	West bet. Secs. 8 & 17.
25.20	To Wild Horse ck., the Reservation Boundary.
<hr/>	
Field Notes of the West boundary of T. 3 N., R. 34 E.	
North on West boundary of Sec. 31.	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec.
80.00	Set post and made mound of earth for cor. to Secs. 30, 31, 25 & 36. Land, level. Soil, good.
<hr/>	
North on West boundary of Sec. 30.	
V. 20°30' E.	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 19, 30, 24 & 25. Land, rolling. Soil, good.
<hr/>	
North on West bdy. Sec. 19.	
V. 21° E.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ S. cor.
80.00	Set post and made mound of earth for cor. to Secs. 18, 19, 13 & 24. Land, rolling. Soil, good.
<hr/>	