

Exteriors of Township 3 North, Range 34 E. W. M.

Chains	<p>1½ ft. high, 3½ ft. base around post.</p>
43.50	<p>Leave field and wire fence, course E.</p>
60.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist. & raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.</p>
80.00	<p>Set a post 48x4x4 ins. 12 ins. in the ground for cor. to Secs. 24, 25, 19 & 30, marked R 35 E S 19 on NE., S 30 on SE., R 34 E S 25 on SW., T 3 N S 24 on NW. faces, with 4 notches on N. & 2 notches on S edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base around post.</p>
	<p>Land, level. Some grass. Soil, 1st rate.</p>
	<p>South on E. bdy., Sec. 25. Var. 20° E.</p>
20.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake, 2 ft. long long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
40.00	<p>Set a post 36x3x3 ins. 12 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base around post.</p>
60.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground & marked 1/16 S on W. face.</p>