

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>it.</p> <p>Land, rolling.</p> <p>Soil, good. Mostly cultivated.</p>
79.84	<p>East on ran. bet. Secs. 1 and 12.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Set temporary cor. at 20, 40 and 60 chains and at Intersect E. bdy. Township at cor. to Secs. 1, 12, 6 and 7. Thence West on true line.</p>
.30	<p>Fence and enter field, N. and S.</p>
19.96	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p>
39.92	<p>Fence N. and S. and set charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>
59.88	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
78.15	<p>Lane, N. and S.</p>
79.84	<p>Cor. to Secs. 1, 2, 11 and 12.</p> <p>Land, level. Soil Soil, good. All cultivated.</p>
Z	<p>South bet. Secs. 11 and 12.</p> <p style="text-align: center;">Va. 21° East.</p>