

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.</p>
39.78	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. in the ground, marked ½ S on N. face.</p>
42.90	Fence, N. and S.
46.50	Lane, N. and S.
53.75	Fence, N. and S.
59.67	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
78.25	Fence, N. and S.
79.56	<p>Cor. to Secs. 12, 13, 11 and 14 Land, rolling. Soil, first rate. All cultivated.</p>
<p>South on true line bet. Secs. 13 and 14. Va. 20° East.</p>	
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
37.25	Leave field E. and W.
40.00	<p>Set charred stake, 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins.</p>