

## Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
60.00	<p>square, 12 ins. in the ground; marked <math>\frac{1}{4}</math> S on W. face.</p> <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it. And in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{16}</math> S on W. face.</p>
76.00	Wagon road, NW.
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 13, 14, 23 and 24, marked T 3 N S 13 on NE., R 34 E S 24 on SE., S 23 on SW. and S 14 on NW. faces with 3 notches on S and 1 notch on E. edges. Dug pits 18x18x12 ins. in each sec., <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base around it.</p> <p>Land, mostly level.</p> <p>Soil, 1st class. Mostly cultivated.</p>
79.40	<p>East on ran. bet. Secs. 13 and 24.</p> <p style="text-align: center;">Va. <math>21^{\circ}</math> East.</p> <p>Set temporary cors. at 20, 40, and 60 chains and at Intersect E. bdy., Township 70 lks. North of cor. to Secs. 13, 24, 18 and 19. Thence N. <math>89^{\circ}30'</math> W. on true line.</p> <p style="text-align: center;">Va. same.</p>
5.00	Wagon road, NE.
7.00	Leave same and enter field.
19.85	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. cor. Dig pits 18x18x12 ins. E. and W. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{16}</math> S on N. face.</p>
20.50	County road, 100 lks. N. and S.
39.70	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, <math>5\frac{1}{2}</math></p>