

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>for cor. to Secs. 23, 24, 25 and 26, mkd. T 3 N S 24 on NE., R 34 E S 25 on SE., S 26 on SW., and S 23 on NW. faces, with 2 notches on S. and 1 notch on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base around cor.</p> <p>Land, level. Soil, 1st rate. All under cultivation.</p>
79.30	<p>East on ran. bet. Secs. 24 and 25.</p> <p style="text-align: center;">Var. 20½° East.</p> <p>Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. Township 70 lks. N. of cor. to Secs. 24, 25, 19 and 30. Thence N. 89°30' W. on true line.</p> <p style="text-align: center;">Va. 20° East.</p>
19.82	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face. Dug pits 18x18x12 ins. E. and W. of post, 5½ ft. dist. Raised md. of earth 1½ ft. high, 3½ ft. base around it.</p>
39.65	<p>Set stone 14x8x6 ins., 8 ins. in the ground for ¼ sec. cor., marked ¼ on N. face. Dug pits 18x18x12 ins. E. and W. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
59.47	<p>Set post 3 ft. long, 3 ins. sq., 24 ins. in the ground for 1/16 S on N. face. Dug pits 18x18x12 ins. E. and W. of post, 5½ ft. dist. and raised md. of earth 1½ ft. high, 3½ ft. base around it.</p>
69.20	<p>Wagon road, N. and S.</p>
79.30	<p>Cor. to Secs. 23, 24, 25 and 26.</p> <p>Land, level or nearly so. Soil, 1st rate. Mostly cultivated. Some good improvements on same.</p>
15.35	<p>South bet. Secs. 25 and 26.</p> <p style="text-align: center;">Va. 20½° East.</p> <p>Wagon road, NE. and SW.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 S. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft.</p>