

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.82	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>
59.73	<p>Deposited charred stake 12 ins. in the ground for 1/16 cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ high, 3½ ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.65	<p>Cor. to Secs. 25, 26, 35 and 36. Land, high and rolling. Soil, 1st rate. But small portion of this mile, cultivated.</p>
<p>South on ran. bet. Secs. 35 and 36.</p>	
<p>Va. 20¼° East.</p>	
80.07	<p>Set temporary cors. at 20, 40 and 60 chains and at Intersect S. bdy., Township 70 lks. E. of cor. to Secs. 35 and 36. Thence N.30' E. on true line.</p>
<p>Va. 22° East.</p>	
15.00	<p>Gulch, NW.</p>
20.07	<p>Set stone 11x10x8 ins. 7 ins. in the ground, marked 1/16 on W. face for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
40.97	<p>Set stone 12x8x6 ins. 8 ins. in the ground for ¼ sec. cor., marked ¼ on W. face. Dug pits 18x18x12 ins. N. and S. of stone, 5½ ft. dist. Raised mound of earth 1½ ft.</p>

-50