

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	Land, mostly level. Soil, 1st rate. Well adapted to agriculture.
80.12	East on ran. bet. Secs. 11 and 14. Va. 21° East. Set temporary cor. at 20, 40 and 60 chains, and at Intersect N. and S. line at cor. to Secs. 11, 12, 13 and 14. Thence West on true line. Va. same.
12.80	Fence, N. and S.
20.03	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.06	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in East pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.
60.09	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.12	Cor. to Secs. 10, 11, 14 and 15. Land, slightly rolling. Soil, 1st rate. Well adapted to agriculture, but little cultivated.
20.00	South bet. Secs. 14 and 15. Va. 20° East. Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½