

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
40.37	<p>sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. in the ground, marked ¼ S. on N. face.</p>
43.25	<p>Wagon road, NE.</p>
60.56	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.75	<p>Cor. to Secs. 14, 15, 22 and 23. Land, slightly rolling. Soil, 1st rate. Not cultivated.</p>
	<p>South bet. Secs. 22 and 23. Va. 20° East.</p>
12.00	<p>Wagon road, NE.</p>
20.00	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>