

Subdivisions of T. 3 North, R. 34 East W.M.

| Chains | <p>12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and marked post $\frac{1}{4}$ S. on W. face.</p> |
|--------|--|
| 41.01 | <p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for Meander cor. to fractional Secs. 3 and 4, marked M.C. with T 3 N on N., R 34 E. S 3 on E., and S 4 on W. faces. Dug a pit 3 ft. square, 12 ins. deep, 8 lks. N. of post and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around it.</p> |
| 41.15 | <p>Wild Horse Creek 10 lks. W.</p> |
| 41.60 | <p>Wagon road, E. and W.</p> |
| 73.00 | <p>O. R. and N. Railway NE.</p> |
| 80.00 | <p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 3, 4, 9 and 10, marked T 3 N S 3 on NE., R 34 E S 10 on SE., S 9 on SW. and S 4 on NW. faces with 5 notches on S. and 3 notches on E. edges. Dug pits 18x18x12 ins. in each sec., $5\frac{1}{2}$ ft. dist, Raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, level. Soil, 1st rate. Partly cultivated.</p> |
| | <p>East on ran. bet. Secs. 3 and 10. Va. 20° E.</p> |
| 80.25 | <p>Set temporary cor. at 20, 40 and 60 chains and at Intersect N. and S. line 10 lks. N. of cor. to Secs. 2, 3, 10 and 11. Thence N. 89°56' West on true line. Va. same.</p> |
| 20.05 | <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> |
| 40.12 | <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$</p> |