

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.</p>
57.50	Fence, N. and S.
80.25	<p>Cor. to Secs. 3, 4, 9 and 10. Land, level. Soil, 1st rate. Partly cultivated.</p>
<p>South bet. Secs. 9 and 10. Va. 20° East.</p>	
40.00	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.</p>
41.50	Leave field E. and W.
79.10	<p>Old mound and pit which I find has been reestablished by the Commissioners on Indian affairs as a D.R. cor. on bdy. of the new Reserve. And after ascertaining this cor. to be due East 80 chains dist. from cor. to Secs. 8, 9, 16 and 17, and knowing that in either case it will not materially change the directions of the E. and W. line in this tier of secs. or the one just West, I reestablish same.</p> <p>Depositing charred stake 12 ins. in the ground for cor. to Secs. 9, 10, 15 and 16. Dug pits 18x18x12 ins. in each sec., $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in SE. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 10 on NE., R 34 E S 15 on SE., S 16 on SW., and S 9 on NW. faces with 4 notches on S. and 3 notches on E. edges.</p> <p>Land, level. Soil, 1st rate. Partly cultivated.</p>