

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
33.00	Wagon road, E. and W.
40.00	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. cor. Dug pits 18x18x12 ins. N. and S. of stake <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{4}</math> S on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
70.75	Spring branch, 5 lks. wide, NE.
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 15, 16, 21 and 22, marked T 3 N S 15 on NE., R 34 E S 22 on SE., S 21 on SW., and S 16 on NW. faces with 3 notches on S. and E. edges. Dug pits 18x18x12 ins. in each sec., <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth 2 ft. high, <math>4\frac{1}{2}</math> ft. base over it.</p> <p>Land, mostly level.</p> <p>Soil, 1st rate. Some alkaline. Not cultivated.</p>
	<p>East on ran. bet. Secs. 15 and 22. Va. 20° E.</p>
80.00	<p>Set temporary cors. at 20, 40 and 60 chains and at Intersect N. and S. line 100 lks. N. of cor. to Secs. 14, 15, 22 and 23. Thence N. 89° 17' W. on true line. Va. same.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of cor., <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in E. pit drove stake 2 ft.</p>