

Subdivisions of T. 3 North, R. 34 East W. M.

|        |                                                                                                                                                                                                                                                                                                                 |
|--------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Chains | <p>long, 2 ins. square, 12 ins. in the ground, marked<br/>1/16 S on N. face.</p>                                                                                                                                                                                                                                |
| 32.50  | Wagon road, NE.                                                                                                                                                                                                                                                                                                 |
| 40.00  | Deposited charred stake 12 ins. in the ground for 1/4 sec.<br>cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 1/2<br>ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2 ft.<br>base over it, and in E. pit drove stake 2 ft. long,<br>2 ins. square, 12 ins. in the ground, marked 1/4 S on<br>N. face.    |
| 60.00  | Deposited charred stake 12 ins. in the ground for 1/16<br>sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,<br>5 1/2 ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2<br>ft. base over it, and in E. pit drove stake, 2 ft.<br>long, 2 ins. square, 12 ins. in the ground, marked<br>1/16 S on N. face. |
| 69.50  | Spring branch, 5 lks. wide NW.                                                                                                                                                                                                                                                                                  |
| 80.00  | Cor. to Secs. 15, 16, 21 and 22.<br>Land, rolling.<br>Soil, 1st rate. Uncultivated.                                                                                                                                                                                                                             |
|        | <p>South bet. Secs. 21 and 22.<br/>Va. 20° East.</p>                                                                                                                                                                                                                                                            |
| 20.00  | Deposited charred stake 12 ins. in the ground for 1/16<br>sec. cor. Dug pits 18x18x12 ins. N. and S. of stake,<br>5 1/2 ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2<br>ft. base over it, and in N. pit, drove stake 2 ft.<br>long, 2 ins. square, 12 ins. in the ground, marked<br>1/16 S on W. face. |
| 40.00  | Deposited charred stake 12 ins. in the ground for 1/4 sec.<br>cor. Dug pits 18x18x12 ins. N. and S. of stake, 5 1/2<br>ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2 ft.<br>base over it, and in N. pit drove stake 2 ft. long,<br>2 ins. square, 12 ins. in the ground, marked 1/4 S on<br>W. face.    |
| 60.00  | Deposited charred stake 12 ins. in the ground for 1/16<br>sec. cor. Dug pits 18x18x12 ins. N. and S. of stake,                                                                                                                                                                                                  |