

Subdivisions of T. 3 North, R 34 East W. M.

Chains	
80.40	<p>5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face and leave field, N, and S.</p> <p>Cor. to Secs. 21, 22, 27 and 28.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Some good dwellings in each sec. Mostly cultivated.</p>
20.00	<p>South bet. Secs. 27 and 28.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 27, 28, 33 and 34, marked T 3 N S 27 on NE., R 34 E S 34 on SE., S 33 on SW., and S 28 on NW. faces with 1 notch on S. and 3 notches on E. edges. Dug pits 18x18x12 ins. in each sec. 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base around it.</p>