

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	West on true line.
	Va. same.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.
49.10	Ditch, NW.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
71.00	Wagon road to Adams.
80.00	Cor. to Secs. 8, 9, 16 and 17. Land, level. Soil, 1st rate. Not cultivated.
	South bet. Secs. 16 and 17. Va. 21° East.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
22.65	Wagon road, NE.
40.00	Set charred stake 12 ins. in the ground for ¼ sec. cor.