

Subdivisions of T. 3 North, R. 34 East W. M.

Chains 40.00	Gulch and Wagon road, N.	-50
72.00	Wagon road, NE.	
75.05	Cor. to Secs. 17, 18, 19 and 20. Land, rolling. Soil, 1st rate. Not cultivated.	
South bet. Secs. 19 and 20. Va. 20° East.		
8.00	County wagon road, NE.	
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.	
62.00	Wagon road, NE.	
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground, marked, T 3 N S 20 on NE., R 34 E S 29 on SE., S 30 on SW., and S 19 on NW. faces with 2 notches on S. and 5 notches on E. edges. for cor. to Secs. 19, 20, 29 and 30. Dug pits 18x18x12 ins. in each sec.; $5\frac{1}{2}$ ft. dist., and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around it. Land, level. Soil, 1st rate. Not cultivated.	
East on ran. bet. Secs. 20 and 29. Va. 20° East.		
79.80	Set temporary cors. at 20, 40 and 60 chains, and at Intersect N. and S. line 20 lks. N. of cor. to Secs. 20, 21, 28 and 29. Thence N. 89°51' W. on true line.	
Va. same.		
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft.	