

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
39.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on West face.</p>
59.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
79.00	<p>Cor. to Secs. 29, 30, 31 and 32. Land, slightly rolling. Soil, 1st rate, sandy loam. Not cultivated.</p>
<p>Aug. 19, 1887</p>	
<p>This township is rolling. The soil is a rich loam, 1st rate. Most of it is in cultivation. There is no timber. Grass, very poor.</p>	
<p>Survey of the Sub-Subdivisional Lines of Township 3 North, Range 34 East Willamette Meridian, Oregon, as surveyed by James P. Currin and James E. Noland, U.S. Deputy Surveyors, under special contract, dated May 4th 1887.</p>	
<p>Survey commenced Oct. 4th 1887. Survey completed Oct. 13th 1887</p>	
79.75	<p>East on random through S. ½ of Sec. 36, T. 33N., R. 34 East. Va. 21° East. Commencing at 1/16 sec. cor., 20 chains S. of ¼ sec. cor. bet. Secs. 35 and 36, set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 33 lks. N. of 1/16 sec. cor. Thence</p>