

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.60	<p>To point of beginning.</p> <p>Land, mostly level. Soil, 1st rate.</p>
	<p>East on random through S ½ of Sec. 25.</p> <p style="text-align: right;">Va. 20¼° East.</p> <p>Commencing at 1/16 sec. cor., 20 chains N. of SW. cor. of Sec. 25. Set temporary cors. at 20, 40 and 60 chains, and at</p>
79.56	<p>Intersect E. bdy. 60 lks. N. of 1/16 sec. cor. Thence N.89°34'W. on true line.</p>
19.89	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.78	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, & in E. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S on N. face.</p>
59.67	<p>Deposited charred stake 12 ins. in the ground for 1/16 S. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised md. of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, mkd. 1/16 S on N. face.</p>
79.56	<p>To point of beginning.</p> <p>Land, mostly level, partly cultivated.</p>
	<p>East on random through center of Sec. 25.</p> <p style="text-align: right;">Va. 20½° East.</p> <p>Commencing at ¼ sec. cor. bet. Secs. 25 & 26. Set temp.</p>