

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	
18.75	Fence and leave field.
19.86	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.72	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. East and West of of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.58	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.44	To point of beginning. Land, rolling. Soil, good. Cultivated.
	East on random through Center of Sec. 13. Va. 20½° East.
79.42	Commencing at ¼ sec. cor. bet. Secs. 13 and 14, set temporary cors. at 20. 40 and 60 chains, and at Intersect E. bdy. 42 lks. N. of 1/16 sec. cor. Thence N.89°42' West on true line.
16.00	Spring branch, 5 lks. wide, runs NW.
17.75	Enter yard of dwelling.
19.80	Dwelling house of Mr. DeFave.
19.85	Point of 1/16 sec. cor. is under house, and set charred stake 12 ins. in the ground, 25 lks. due S. of true cor. for witness cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½