

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.94	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.92	To point of beginning. Land, level. Soil, good. All cultivated.
East on random through Center of Sec. 1. Va. 21° East.	
79.90	Beginning at ¼ sec. cor. bet. Secs. 1 and 2. Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. at ¼ sec. cor. Thence West on true line.
19.98	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.95	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, sq., 12 ins. 2 ins./in the ground, marked ¼ S on N. face.
59.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½