

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.90	To point of beginning. Soil, 1st rate. Land, level. All cultivated.
East on random through N. $\frac{1}{2}$ of Sec. 1. Va. $21\frac{1}{4}^{\circ}$ East.	
	Beginning at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 1 and 2, set temporary cors. at 20, 40 and 60 chains, and at
79.96	Intersect E. bdy. 7 lks. N. of 1/16 sec. cor. Thence N. $89^{\circ}57'$ W. on true line.
.50	Fence N. and S. and enter field.
19.99	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.96	To point of beginning. Land, slightly rolling. No water. Soil, 1st rate. All cultivated. Good farming land. Oct. 5, 1887