

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.40	To point of beginning.
	Land, rolling.
	Soil, good. Oct. 6, 1887.
<hr/> East on random through Center of Sec. 26. Va. 20 $\frac{1}{2}$ ° East.	
	Beginning at $\frac{1}{4}$ sec. cor. bet. Secs. 26 and 27.
	Set temporary cors. at 20, 40 and 60 chains, and at
80.20	Intersect E. bdy. 7 lks. S of $\frac{1}{4}$ sec. cor. Thence S. 89°-57' W. on true line.
20.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
40.10	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
60.15	Deposited charred stake in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.20	To point of beginning.
	Land, level.
	Soil, 1st rate. Good grass. No water.
<hr/> East on random through N. $\frac{1}{2}$ of Sec. 26. Va. 20 $\frac{1}{2}$ ° East.	