

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>East on random through Center of Sec. 14.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Beginning at $\frac{1}{4}$ sec. cor. bet. Secs. 14 and 15, set temporary cors. at 20, 40 and 60 chains, and at</p> <p>80.40 Intersect E. bdy. at $\frac{1}{4}$ sec. cor. Thence</p> <p>West on true line</p> <p>20.10 Deposited charred stake 12 ins. in the ground for sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>40.20 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.</p> <p>60.30 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground for 1/16 S on N. face.</p> <p>80.40 To point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>East on random through N. $\frac{1}{2}$ of Sec. 14.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Beginning at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 14 and 15, set temporary cors. at 20, 40 and 60 chains, and at</p> <p>80.20 Intersect E. bdy. 7 lks. S. of 1/16 sec. cor. Thence S.89°57' W. on true line.</p> <p>20.05 Deposited charred stake 12 ins. in the ground for 1/16</p>