

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
60.50	<p>Gulch, NW.</p>
80.00	<p>To point of beginning. Land, level mostly. Soil, 1st rate.</p>
<p>East on random through Center of Sec. 11 Va. 20° East.</p>	
79.67	<p>Beginning at ¼ sec. cor. bet. Secs. 10 and 11, set temporary sec. cor. at 20, 40 and 60 chains, and at Intersect E. bdy. 7 lks. N. of ¼ sec. cor. Thence N.89°57' W. on true line.</p>
19.92	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p>
38.00	<p>Fence, bears N. and S.</p>
39.84	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>
59.76	<p>Deposited charred stake 12 ins. in the ground for 1/16</p>

-100