

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	marked 1/16 S on N. face.
39.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
59.88	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
79.84	To point of beginning. Land, level. Soil, 1st rate. Oct. 11, 1887.
East on random through S. ¼ of Sec. 34. Va. 21° East.	
Commencing at 1/16 sec. cor. 20 chains S. of ¼ sec. cor. bet. Secs. 33 and 34, set temporary cors. at 20, 40 and 60 chains, and at	
79.80	Intersect E. bdy. 60 lks. N. of 1/16 sec. cor. Thence N. 89° 34' W. on true line.
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, sq. 12 ins. 2 ins/ in the ground, marked 1/16 S on N. face.
25.00	Canon bears SE.
39.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face. Raised mound of earth, 1½ ft.