

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S. on N. face.</p>
60.00	Leave field, N. and S.
79.80	To point of commencement.
	Land, rolling.
	Soil, 1st rate. Partly, cultivated.
East on random through Center of Sec. 34.	
Va. $20\frac{1}{2}^{\circ}$ East.	
	Commencing at $\frac{1}{4}$ sec. cor. bet. Secs. 33 and 34, set temporary cors. at 20, 40 and 60 chains, and at
79.96	Intersect E. bdy. 70 lks. N. of $\frac{1}{4}$ sec. cor. Thence N. $89^{\circ}30'$ West on true line.
12.00	Fence and leave field,
19.99	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor., and dug pits $18 \times 18 \times 12$ ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.
39.98	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
42.00	Canon bears S.
59.97	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of Earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.
79.96	To point of beginning.