

Sub-Subdivisions of T. 3 North, R. 34 East

Chains		
80.20	Intersect E. bdy. 67 lks. N. of 1/16 sec. cor. Thence N.89°31' W. on true line	
10.00	Top of ridge N. and S.	+20
20.05	Set basalt stone 10x10x10 ins. 6 ins. in the ground for 1/16 sec. cor. marked 1/16 S on N. face. Dug pits 18x18x12 ins. E. and W. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it.	
30.00	Canon bears, NW.	-50
40.10	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. East and West of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
52.00	Gulch, N.	-20
60.15	Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., and raised mound of earth and stone, 2 ft. high, 4½ ft. base over it.	
80.20	To point of beginning. Land, rolling. Soil, 1st rate. Not under cultivation.	
	East on random through Center of Sec. 27. Va. 20° East. Commencing at ¼ sec. cor. bet. Secs. 27 and 28, set temporary cors. at 20, 40 and 60 chains, and at	
80.30	Intersect E. bdy. 65 lks. N. of ¼ sec. cor. Thence N.89°32' W. on true line.	
20.07	Set basalt stone 10x8x8 ins. 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face. Dug pits 18x18x12 ins. East and West of stake, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.	
29.30	Enter field	