

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	and 60 chains, and at
80.12	Intersect E. bdy. 100 lks. N. of 1/16. Thence N.89°17' West on true line.
20.03	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.06	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
44.40	Wagon road, bears N.
53.00	Gulch and spring branch bears N.
53.50	Wagon road bears N.
60.09	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.12	To point of beginning. Land, rolling. Soil, 1st rate. Partly cultivated.
<p>East on random through S. ½ of Sec. 15. Va. 20¼° East.</p>	
<p>Beginning at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 15, set temporary cors. at 20, 40 and 60 chains, and at</p>	
80.00	Intersect E. bdy. 100 lks. N. of 1/16 sec. cor. Thence N.89°17'W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16

-75