

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	Commencing at 1/16 sec. cor. 20 chains S. of $\frac{1}{4}$ sec. cor. bet. Secs. 32 and 33, set temporary cors. at 20, 40 and 60 chains, and at	
79.95	Intersect E. bdy. 15 lks. S. of 1/16 sec. cor. Thence S.89°54' W. on true line.	
19.99	Deposited a stone 9x8x7 ins., 6 ins. in the ground for 1/16 sec. cor., mkd. 1/16 on N. face, & raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
30.00	Canon, S.	-100
39.97	Set basalt stone 10x9x8 ins. 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face, and dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
59.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
64.00	Canon, bears S.	-100
79.95	To point of beginning. Land, rolling. Soil, 2nd rate. Not cultivated.	
East on random through Center of Sec. 33.		
Va. 20° East		
Beginning at $\frac{1}{4}$ sec. cor. bet. Secs 32 and 33. Set temporary cors. at 20, 40 and 60 chains, and at		
79.90	Intersect E. bdy. at $\frac{1}{4}$ sec. cor. Thence West on true line	
19.95	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked	