

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>33.00 Indians' House, 50 lks. S. of line.</p> <p>39.93 Deposited charred stake 12 ins. in ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>59.89 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>79.87 To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.</p>
	<p>East on random through Center of Sec. 21. Va. 20½° East.</p> <p>Commencing at ¼ sec. cor. bet. Secs. 20 and 21. Set temporary cors. at 20, 40 and 60 chains, and at</p> <p>79.80 Intersect E. bdy. 9 lks. N. of ¼ sec. cor. Thence N.89°56' W. on true line</p> <p>19.95 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>39.90 Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on</p>