

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 40.00	Deposited charred stake 12 ins. in the ground for the 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
*80.00	To point of beginning. Land, level. Soil, 1st rate. Not cultivated. Oct. 11th 1887,
East on random through S. ½ of Sec. 32. Va. 20½° East.	
Commencing at 1/16 sec. cor. 20 chains S. of ¼ sec. cor. bet. Secs. 31 and 32, set temporary cors. at 20, 40 and 60 chains, and at	
79.84	Intersect E. bdy. 13 lks. N. of 1/16 sec. cor. Thence N.89°54' W. on true line.
19.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
27.50	Canon, bears S.
39.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.