

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 59.88	Set basalt stone 10x9x7 ins. 6 ins. in the ground for 1/16 sec. cor. Marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stone, 5½ ft. dist., and raised mound of earth, 1½ ft. high, 3½ ft. base over it.
79.84	To point of beginning. Land, rolling. Soil, 1st rate. Not cultivated.
East on random through Center of Sec. 32. Va. 20° East.	
80.00	Commencing at ¼ sec. cor. bet. Secs. 31 and 32, set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 10 lks. N. of ¼ sec. cor. Thence N.89°56' W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
30.00	Canon bears SW.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.00	To point of beginning. Land, rolling.