

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	and at
80.28	Intersect E. bdy. 12 lks. N. of 1/16 sec. cor. Thence N.89°55' W. on true line.
20.07	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.14	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
50.30	Wagon Road bears N. and S.
60.21	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.28	To point of beginning.
	Land, level.
	Soil, 1st rate.
East on random through Center of Sec. 29.	
Va. 20° East.	
Commencing at ¼ sec. cor. bet Secs. 29 and 30, set temporary cors. at 20, 40 and 60 chains, and at	
80.00	Intersect E. bdy. 15 lks. N. of ¼ sec. cor. Thence N. 89°54' W. on true line.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft.