

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 1/2 ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/4 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 1/2 ft. dist. Raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.00	To point of commencement. Land, level. Soil, 1st rate. Not cultivated.
East on random through N. 1/2 of Sec. 29. Va. 20° East.	
Commencing at 1/16 sec. cor. 20 chains N. of 1/4 sec. cor. bet. Secs. 29 and 30, set temporary cors. at 20, 40 and 60 chains, and at	
79.88	Intersect E. bdy. 20 lks. N. of 1/16 sec. cor. Thence N.89°51'W. on true line.
19.97	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 1/2 ft. dist. Raised md. of earth 1 1/2 ft. high, 3 1/2 ft. base over it, & in E. pit drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, mkd. 1/16 S on N. face.
39.94	Deposited charred stake 12 ins. in the ground for 1/16 S. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 1/2 ft. dist. Raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.