

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	
74.50	<p>ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Not cultivated.</p>
74.60	<p>West on random through Center of Sec. 30.</p> <p style="text-align: center;">Va. 20° East.</p> <p>Commencing at <math>\frac{1}{4}</math> section corner between Secs. 29 and 30, set temporary corners at 20, 40 and 60 chains, and at</p> <p>Intersect W. bdy., Township, 102 lks. S. of <math>\frac{1}{4}</math> sec. cor.</p> <p>Thence</p> <p>N. 89°14' E. on true line.</p>
14.60	<p>Deposited charred stake 12 ins. in the ground for 1/16 section corner. Dug pits 18x18x12 ins. East and West of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth, 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in East pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
32.00	<p>Wagon road, bears N. and S.</p>
34.60	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. cor. Dug pits 18x18x12 ins. East and West of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in East pit drove stake, 2 feet long, 2 inches square, 12 inches in the ground, marked <math>\frac{1}{4}</math> S on N. face.</p>
54.60	<p>Deposited charred stake 12 inches in the ground for 1/16 section corner. Dug pits 18x18x12 inches East and West of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth, 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in East pit drove stake, 2 ft. long, 2 inches square,</p>