

Topography of T. 3 North, R. 34 East

Chains 58.12	Gulch, course NW.
	<p style="text-align: center;">_____</p> <p>From Cor. to Secs. 34 &amp; 35, a stone 10x8x8. Going North between Secs. 34 &amp; 35, I find no gulch crossing line.</p>
	<p>From cor. to Secs. 15, 16, 21 &amp; 22, a charred stake with stake in SE. pit, marked S 15 T 3 N on NE., S 22 R 34 E on SE., S 21, SW., &amp; S 16 on NW., with 3 notches on S. &amp; E. edges. Pits &amp; mound, well preserved.</p>
	West bet. Secs. 16 & 21.
	Var. 21° E.
1.50	A road, course NW. & SE.
	From same corner, South bet. Secs. 21 & 22
1.55	A road, course NW. & SE.
	From same cor. North bet. Secs. 15 & 16.
5.00	A branch runs NW.
	<p>Find cor., Secs. 16, 17, 20 &amp; 21 to be a post, 20x4x4 above ground, marked S 16 T 3 N on NE., S 21 R 34 E on SE., S 20 on SW., S 17 on NW. Notches, if any, decayed off. Cut 4 notches on East &amp; 3 on S. edges. Pits, partly filled &amp; md. mostly gone.</p>
	North between Secs. 16 & 17.
	Va. 21° E.
40.00	Find $\frac{1}{4}$ sec. cor. in good condition.
42.35	An abandoned road, course NE. & SW.
60.00	1/16 cor. gone.
62.00	Enter Pendleton & Athena Road, course NE.
64.85	Leave Pendleton & Athena Road, course NE.
80.00	<p>To cor., Secs. 8, 9, 16 &amp; 17, a post 2 ft. x 4 ins. square above ground. Mound gone &amp; pits filled by sand. Post marked S 9 T 3 N on NE., S 16 R 34 E on SE., S 17 on SW., S 8 on NW., D R on E. I cut 4 notches on E. &amp; S. edges.</p>
	Sec. 16,
	East through North half of Sec. 16